

CITY OF CONWAY  
CONWAY SANITATION DEPARTMENT  
SANITARY LANDFILL  
BOTTOM LINER PREPARATION ZONES 18 & 19  
CONWAY, ARKANSAS

Prepared By  
Conway Street & Engineering Department  
Conway, Arkansas  
501-450-6165

ADDENDUM NO. 1

August 2, 2010

A. PURPOSE

The purpose of this Addendum No. 1 is to revise the Unit Price Schedule by eliminating Item No. 4 – Trench & Excavation Safety as shown in the Proposal on Sheet P-2 of the project “Specification and Contract Documents”. In addition, a list of statements is made in response to questions submitted regarding this project.

B. SPECIFICATIONS AND CONTRACT DOCUMENTS  
PROPOSAL  
UNIT PRICE SCHEDULE

Remove Item No. 4 – Trench & Excavation Safety from the Unit Price Schedule as shown on sheet P-2 of the Proposal by striking a line thru or “xing out” this Item and associated “Unit Price Bid” and “Amount”.

C. CLARIFICATION STATEMENTS:

- The Clay liner material may be obtained from a material stockpile adjacent to the project work area. The stockpile is within 500 feet of the Project Work Area.
- The hydraulic conductivity of the clay liner shall not be more permeable than  $1 \times 10^{-7}$  cm/sec.
- The perimeter berm on the northern and western side of the project shall remain in place after construction is complete.
- Fabric having equal characteristics and properties to Mirafi 140 NL will be acceptable.
- As stated in Section 3 of the Specifications, any additional excavation required for removal of unsuitable material will be measured and paid for as “Site Excavation for Zones 18 & 19”. Fill or embankment required to replace unsuitable material or fill required to achieve the bottom elevation of the clay liner will be measured and paid for as “Place & Compact Bottom Clay Liner”.

D. ACKNOWLEDGEMENT

The bidder should note in the space provide on Sheet P-6 of the Proposal the receipt of this Addendum No. 1.